



D.V. Electromatic (P) Ltd.



AN ISO 9001:2008 CERTIFIED CO.

REF NO: **DVEPL/20-21/6414/0**

Date – 10-September-2024

TO,
MES

Kind Attn.: XXX
Mobile No.: XXX
Email ID: XXX

Sub: **QUOTATION FOR LT PANEL CEJZ_JRC- _2023-24 (2023_MES_604157_1)**

Dear Sir,

We acknowledge with thanks the receipt of your valued enquiry regarding above mentioned subject. We are pleased to furnish our most competitive offer for your favorable consideration as under.

ANNEXURE - I: FABRICATION DETAILS & TECHNICAL SPECIFICATIONS

ANNEXURE - II: BILL OF MATERIAL

ANNEXURE- III: PRICE SCHEDULE

ANNEXURE- IV: TERMS AND CONDITIONS

We hope the detailed BOQ & Tech Specs here under is as per your requirement.

Should you need any further clarification(s) please feel free to contact us. We look forward for an opportunity to serve you.

Thanking you,

Yours faithfully,

For **D.V. ELECTROMATIC PVT. LTD.**

Authorized Signatory

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M | +91 94170 21685, +91 94176 01244
E | dvepl@yahoo.in, office@dvepl.com
W | www.dvepl.com



ANNEXURE – I

TECHNICAL SPECIFICATIONS

- 1. Material of Sheet:** CRCA sheet
- 2. Sheet thickness:** AS PER TENDER thickness for All Panels.
- 3. Material treatment:** Thorough chemical treatment with 7 tank process method for degreasing, derusting and phosphating powder coating shall not be less than 40 microns.
- SIEMENS GREY (RAL-7032) shade powder coating paint will be applied.
- 4. Bus bar:** The bus bars will be insulated with PVC heat shrinkable sleeves and supported SMC/DMC at Suitable intervals so as to withstand dynamic stresses developed in the event of short circuit of 50ka (RMS) and will withstand following standard tests:-
- (a) Continuity tests
(b) No load operation test
(c) H.T Test (2kV) for one minute.
(d) Insulation resistance test.
- 6. Fault Level:** 35 KA
- 7. Bus Bar Size:** As per BOQ
- 8. Current Density:** 0.8A/Sq. mm. Current Density.
- 9. Bus bar insulation** Heat Shrinkable Sleeves

MANUFACTURERS OF LT CONTROL PANELS

**ANNEXURE – II****BILL OF MATERIALS**

1	SR NO 7.32		BOARD QTY		
A	INCOMER MCCB 125A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	125A 4P 25kA MCCB (with Spreaders), TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1125C4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 125-160A TAB1 MCCB	HPL	TAB1160ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Ammeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1310100000	1	1
2	Voltmeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1320100000	1	1
3	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
4	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
5	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
6	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	1	1
7	125/5A 1VA Acc. CL: 1, ABS Insulated Bar Primary Rectangular Current Transformer, ID: 30x10mm	NIPPEN	NE 301	3	3
8	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
9	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
C	CHANGE OVER 100A	MAKE	1	FEEDER QTY	1
1	100A 4P Front Operated On Load Changeover Switch, Open Execution	HPL	CDC01004POAV	1	1
D	STAR DELTA 45HP	MAKE	1	FEEDER QTY	1
1	100A 3P 25kA MCCB (with Spreaders), TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1100C3P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
3	AC3: 80A AC1: 110A 3P Power Contactor, Coil Voltage: 220V AC, Aux. contact: 1NO+1NC, Type: SDE-80	HPL	SDE8011A4	3	3
4	63-80A Thermal Overload Relay, Aux. Contact: 1NO + 1NC, Contactor Type: SDE Contactor, Type: SDER93	HPL	SDER93/80.0	1	1
5	Star Delta Timer, Time Setting: 3sec - 120sec, Voltage: 240V AC - 415V AC, Contact: 1CO (Star) + 1CO (Delta)	GIC	14SDT1S	1	1
6	SPP + Selectable Under Voltage+Selectable Over Voltage Relay ON Delay 0 - 15Sec,Phase 10% fixed Asymmetry, Voltage: 240 VAC,2 C/O, 3Ph/1Ph 4W, Type: SM500	GIC	MG73BH	1	1
7	Red Flush Head Push Button 22.5 mm	ESBEE	EMNRFD1	1	1
8	Green Flush Head Push Button 22.5 mm	ESBEE	EMNGFD1	1	1
9	1NO Contact Block	ESBEE	EC1C	1	1
10	1NC Contact Block	ESBEE	EC2C	1	1
11	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
12	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
13	Amber Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLA240A	1	1
14	6A 1P 2Way Local - Remote/ Auto-Manual Switch with Center OFF, 60 Deg. Operation	SALZER	61025SAB13	1	1
E	OUTGOING MCCB 100A	MAKE	1	FEEDER QTY	1
1	100A 4P 25kA MCCB (with Spreaders), TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1100C4P	1	1

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
F	OUTGOING MCCB	MAKE	1	FEEDER QTY	2
1	32A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC32	1	2
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 3MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 60X60X6MM & 600MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x20x10, N: 1X20X10 Material: Electrolytic grade Aluminum Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Aluminum	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB
2	SR NO 8.03		BOARD QTY		
A	INCOMER MCCB 400A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	400A 4P 36kA MCCB (with Spreaders), TM Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 3	HPL	TABBASIX3400N4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 400A TAB3 MCCB	HPL	TAB3400ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, kVAR, kWh, kVAh, kVARh, Runhours, On hours, Phase angle, Interrupts, THD, Events (High-Low), Neutral Current, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4410100000	1	1
2	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
3	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
4	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
5	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	1	1
6	400/5A 10VA Acc. Cl: 1, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 60mm	NIPPEN	NA	3	3
7	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
8	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
C	OUTGOING MCCB 200A	MAKE	1	FEEDER QTY	1
1	200A 4P 25kA MCCB (with Spreaders), TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 2	HPL	TABBASIX2200C4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 160-200A TAB2 MCCB	HPL	TAB2200ST4P	1	1
D	OUTGOING MCCB 100A	MAKE	1	FEEDER QTY	1
1	100A 4P 16kA MCCB (with Spreaders), TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1100D4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
E	OUTGOING MCCB 40A	MAKE	1	FEEDER QTY	2
1	40A 4P 16kA MCCB, TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1040D4P	1	2
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	2
F	OUTGOING MCCB	MAKE	1	FEEDER QTY	1

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



1	32A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC32	1	1
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 3.15 CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X5 MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x30x10, N: 1X30X10 Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB
2	SR NO 8.04		BOARD QTY		
A	INCOMER MCCB 160A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	160A 4P 25kA MCCB (with Spreaders), TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1160C4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 125-160A TAB1 MCCB	HPL	TAB1160ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, kVAR, kWh, kVAh, kVARh, Runhours, On hours, Phase angle, Interrupts, THD, Events (High-Low), Neutral Current, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4410100000	1	1
2	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
3	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
4	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
5	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	1	1
6	200/5A 5VA Acc. Cl: 1, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 34mm	NIPPEN	NA	3	3
7	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
8	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
D	OUTGOING MCCB 100A	MAKE	1	FEEDER QTY	3
1	100A 4P 16kA MCCB (with Spreaders), TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1100D4P	1	3
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	3
E	OUTGOING MCCB 40A	MAKE	1	FEEDER QTY	2
1	40A 4P 16kA MCCB, TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1040D4P	1	2
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	2
F	OUTGOING MCB	MAKE	1	FEEDER QTY	1
1	40A 3PN 10kA C-Curve Techno MCB	HPL	NTTPNC40	1	1
2	32A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC32	2	2
	STREET LIGHT TIMER	MAKE	1	FEEDER QTY	1
1	20A 3P 10kA C-Curve Techno MCB	HPL	NTTPC20	1	1
2	AC3: 18A AC1: 32A 3P Power Contactor, Coil Voltage: 220V AC, Aux. contact: 1NO+1NC, Type: SDE-18	HPL	SDE1811A4	1	1
3	Digital Time Switch (Crono),Voltage: 110 - 240VAC, Contact: 1 C/O, Base/DIN,	GIC	67DDT0	1	1

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



	25 ON/OFF				
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 3.15MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X5 MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x30x5, N: 1X30X5 Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB
2	SR NO 8.05		BOARD QTY		
A	INCOMER MCCB 100A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	100A 4P 16kA MCCB (with Spreaders), TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160DX100AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, kVARh, kWh, kVAh, kVARh, Runhours, On hours, Phase angle, Interrupts, THD, Events (High-Low), Neutral Current, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4410100000	1	1
2	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
3	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
4	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
5	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	1	1
6	100/5A 5VA Acc. Cl: 1, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 33mm	NIPPEN	NA	3	3
7	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
8	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
D	OUTGOING MCCB 63A	MAKE	1	FEEDER QTY	1
1	63A 4P 16kA MCCB, TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1063D4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
E	OUTGOING MCCB 40A	MAKE	1	FEEDER QTY	2
1	40A 4P 16kA MCCB, TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1040D4P	1	2
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	2
F	OUTGOING MCB	MAKE	1	FEEDER QTY	3
1	32A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC32	1	3
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax I +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M I +91 94170 21685, +91 94176 01244
E I dvepl@yahoo.in, office@dvepl.com
W I www.dvepl.com



1	FABRICATION : 3.15MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X5 MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x20x5, N: 1X20X5 Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB
2	SR NO 8.06		BOARD QTY		
A	INCOMER MCCB 40A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	40A 4P 16kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160DX040AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, kVAR, kWh, kVAh, kVARh, Runhours, On hours, Phase angle, Interrupts, THD, Events (High-Low), Neutral Current, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4410100000	1	1
2	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
3	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
4	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
5	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	1	1
6	50/5A 3VA Acc. CL: 5, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 33mm	NIPPEN	NA	3	3
7	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
8	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
F	OUTGOING MCB	MAKE	1	FEEDER QTY	4
1	32A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC32	1	4
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 3.15MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X5 MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x20x3, N: 1X20X3 Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB
2	SR NO 8.07		BOARD QTY		
A	INCOMER MCCB 63A		1	FEEDER QTY	1

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax I +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M I +91 94170 21685, +91 94176 01244
E I dvepl@yahoo.in, office@dvepl.com
W I www.dvepl.com



SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	63A 4P 16kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160DX063AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, kVAR, kWh, kVAh, kVARh, Runhours, On hours, Phase angle, Interrupts, THD, Events (High-Low), Neutral Current, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4410100000	1	1
2	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
3	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
4	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
5	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	1	1
6	75/5A 3VA Acc. Cl: 5, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 33mm	NIPPEN	NA	3	3
7	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
8	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
F	OUTGOING MCB	MAKE	1	FEEDER QTY	1
1	40A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC40	1	1
2	32A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC32	8	8
	STREET LIGHT	MAKE	1	FEEDER QTY	1
1	20A 3P 10kA C-Curve Techno MCB	HPL	NTTPC20	1	1
2	Spreader Terminals (3 Pole - Set of 6 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST3P	1	1
3	AC3: 18A AC1: 32A 3P Power Contactor, Coil Voltage: 220V AC, Aux. contact: 1NO+1NC, Type: SDE-18	HPL	SDE1811A4	1	1
4	Digital Time Switch (Crono),Voltage: 110 - 240VAC, Contact: 1 C/O, Base/DIN, 25 ON/OFF	GIC	67DDT0	1	1
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 3.15MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X5 MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x20x3, N: 1X20X3 Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB
2	SR NO 8.08		BOARD QTY		
A	INCOMER MCCB 40A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	40A 4P 16kA MCCB, TA Release (Fixed Thermal & Fixed Magnetic), Type : TAB Basix 1	HPL	TABBASIX1040D4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, kVAR, kWh, kVAh, kVARh, Runhours, On hours, Phase angle, Interrupts, THD, Events (High-Low), Neutral Current, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4410100000	1	1
2	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



3	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
4	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
5	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	1	1
6	50/5A 3VA Acc. Cl: 5, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 33mm	NIPPEN	NA	3	3
7	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
8	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
F	OUTGOING MCB	MAKE	1	FEEDER QTY	1
1	40A 3PN 10kA C-Curve Techno MCB	HPL	NTTPNC40	1	1
2	32A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC32	5	5
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 3.15MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X5 MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x20x3, N: 1X20X3, Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax I +91 186 2231231

Factory :
F03, F04, F21,Industrial Growth
Centre,Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M I +91 94170 21685, +91 94176 01244
E I dvepl@yahoo.in, office@dvepl.com
W I www.dvepl.com



ANNEXURE - III

PRICE SCHEDULE

SR. NO.	DESCRIPTION OF ITEM	QTY	UNIT RATE (INR)	AMOUNT (INR)
1	SR NO 7.32	1	76,100.00	76,100.00
2	SR NO 8.03	1	1,04,700.00	1,04,700.00
3	SR NO 8.04	1	92,500.00	92,500.00
4	SR NO 8.05	1	53,000.00	53,000.00
5	SR NO 8.06	1	40,400.00	40,400.00
6	SR NO 8.07	1	42,900.00	42,900.00
7	SR NO 8.08	1	38,100.00	38,100.00
TOTAL QUANTITY		7	TOTAL COST (INR)	4,47,700.00

In words: Rupees Four Lac Forty Seven Thousand Seven Hundred Only

NOTES:

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax | +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M | +91 94170 21685, +91 94176 01244
E | dvepl@yahoo.in, office@dvepl.com
W | www.dvepl.com



ANNEXURE – IV

COMMERCIAL TERMS AND CONDITIONS

PRICE:	Ex works – IGC PATHANKOT (PB.)
PACKING & FORWARDING:	Extra as per actual
FREIGHT & INSURANCE:	Extra Freight & insurance.
GST:	18% or Actual As per Gst Taxation.
OCTROI:	Extra as applicable.
PAYMENT TERMS:	50% in advance with confirmed order and balance against Performa invoice before dispatch.
ORDER PLACEMENT:	D.V. ELECTROMATIC PVT.LTD
DELIVERY:	6-8 Weeks from the date of approval of drawings.
VALIDITY	Our offer is valid for 15 Days from the date of this offer and thereafter subject to our confirmation.
WARRANTY:	18 Months from the date of supply or 12 months from the commissioning whichever ends earlier.
INSPECTION:	On intimation, prior inspection of the panels, if required, may be carried out by the buyers authorized representative at our works at IGC - Pathankot (pb.)
ORDER AMENDMENTS:	Any change in specifications & other terms shall entail revision of delivery and prices including statutory variations.
FORCE MAJEURE:	We shall not be responsible for the failure or delay in order due to acts beyond our control such as war, fire, labour problems, accidents, natural calamities, government acts or shortage of material.
COMMISSIONING CHARGES	2500/Men days Testing, Commissioning and programming with Logging, fooding and boarding in Customer scope. Unloading, Fixing, Laying cables and Installation of panels at site are not in our scope.

Our Bank Details:

HDFC Bank
DALHOUSIE ROAD, PATHANKOT-145001
A/c # 50200012824476
IFSC Code: HDFC0002459

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax | +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M | +91 94170 21685, +91 94176 01244
E | dvepl@yahoo.in, office@dvepl.com
W | www.dvepl.com