



D.V. Electromatic (P) Ltd.



AN ISO 9001:2008 CERTIFIED CO.

REF NO: **DVEPL/20-21/6888/R0**

Date – 16-November-2024

TO,

CWE Shillong - MES

Kind Attn.: XXXXX

Mobile No.: XXXX

Email ID:

**Sub: QUOTATION FOR LT PANEL CWE- SHL-T-65 OF 2024-2025
(2024_MES_680257_1)**

Dear Sir,

We acknowledge with thanks the receipt of your valued enquiry regarding above mentioned subject. We are pleased to furnish our most competitive offer for your favorable consideration as under.

ANNEXURE - I: FABRICATION DETAILS & TECHNICAL SPECIFICATIONS

ANNEXURE- II: PRICE SCHEDULE

ANNEXURE- III: TERMS AND CONDITIONS

We hope the detailed BOQ & Tech Specs here under is as per your requirement.

Should you need any further clarification(s) please feel free to contact us. We look forward for an opportunity to serve you.

Thanking you,

Yours faithfully,

For **D.V. ELECTROMATIC PVT. LTD.**

Authorized Signatory

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M | +91 94170 21685, +91 94176 01244
E | dvepl@yahoo.in, office@dvepl.com
W | www.dvepl.com



ANNEXURE – I

TECHNICAL SPECIFICATIONS

- 1. Material of Sheet:** CRCA sheet
- 2. Sheet thickness:** AS PER TENDER thickness for All Panels.
- 3. Material treatment:** Thorough chemical treatment with 7 tank process method for degreasing, derusting and phosphating powder coating shall not be less than 40 microns.
- SIEMENS GREY (RAL-7032) shade powder coating paint will be applied.
- 4. Bus bar:** The bus bars will be insulated with PVC heat shrinkable sleeves and supported SMC/DMC at Suitable intervals so as to withstand dynamic stresses developed in the event of short circuit of 50ka (RMS) and will withstand following standard tests:-
- (a) Continuity tests
(b) No load operation test
(c) H.T Test (2kV) for one minute.
(d) Insulation resistance test.
- 6. Fault Level:** 35 KA
- 7. Bus Bar Size:** As per BOQ
- 8. Current Density:** 0.8A/Sq. mm. Current Density.
- 9. Bus bar insulation** Heat Shrinkable Sleeves



ANNEXURE – II

PRICE SCHEDULE

SR. NO.	DESCRIPTION OF ITEM	QTY	UNIT RATE (INR)	AMOUNT (INR)
1	SR NO 19	2	66,450.00	1,32,900.00
2	SR NO 20	1	63,400.00	63,400.00
3	SR NO 21	3	80,533.33	2,41,600.00
4	SR NO 22	1	1,24,800.00	1,24,800.00
TOTAL QUANTITY		7	TOTAL COST (INR)	5,62,700.00

In words: Rupees Five Lac Sixty Two Thousand Seven Hundred Only

NOTES:

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax | +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M | +91 94170 21685, +91 94176 01244
E | dvepl@yahoo.in, office@dvepl.com
W | www.dvepl.com



ANNEXURE – III

COMMERCIAL TERMS AND CONDITIONS

PRICE:	Ex works – IGC PATHANKOT (PB.)
PACKING & FORWARDING:	Extra as per actual
FREIGHT & INSURANCE:	Extra Freight & insurance.
GST:	18% or Actual As per Gst Taxation.
OCTROI:	Extra as applicable.
PAYMENT TERMS:	50% in advance with confirmed order and balance against Performa invoice before dispatch.
ORDER PLACEMENT:	D.V. ELECTROMATIC PVT.LTD
DELIVERY:	6-8 Weeks from the date of approval of drawings.
VALIDITY	Our offer is valid for 15 Days from the date of this offer and thereafter subject to our confirmation.
WARRANTY:	18 Months from the date of supply or 12 months from the commissioning whichever ends earlier.
INSPECTION:	On intimation, prior inspection of the panels, if required, may be carried out by the buyers authorized representative at our works at IGC - Pathankot (pb.)
ORDER AMENDMENTS:	Any change in specifications & other terms shall entail revision of delivery and prices including statutory variations.
FORCE MAJEURE:	We shall not be responsible for the failure or delay in order due to acts beyond our control such as war, fire, labour problems, accidents, natural calamities, government acts or shortage of material.
COMMISSIONING CHARGES	2500/Men days Testing, Commissioning and programming with Logging, fooding and boarding in Customer scope. Unloading, Fixing, Laying cables and Installation of panels at site are not in our scope.

Our Bank Details:

HDFC Bank
DALHOUSIE ROAD, PATHANKOT-145001
A/c # 50200012824476
IFSC Code: HDFC0002459

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax | +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M | +91 94170 21685, +91 94176 01244
E | dvepl@yahoo.in, office@dvepl.com
W | www.dvepl.com