



REF NO: **DVEPL/24-25/6929/R0** 

Date - 03-December-2024

TO,

**GE JAMMU - MES** 

Kind Attn.: XXXXX Mobile No.: XXXXX

Email ID:

Sub: QUOTATION FOR LT PANEL GEJC-66\_2024-25 (2024\_MES\_679454\_1)

Dear Sir,

We acknowledge with thanks the receipt of your valued enquiry regarding above mentioned subject. We are pleased to furnish our most competitive offer for your favorable consideration as under.

ANNEXURE - I: FABRICATION DETAILS & TECHNICAL SPECIFICATIONS

ANNEXURE- II: PRICE SCHEDULE

ANNEXURE- III: TERMS AND CONDITIONS

We hope the detailed BOQ & Tech Specs here under is as per your requirement.

Should you need any further clarification(s) please feel free to contact us. We look forward for an opportunity to serve you.

Thanking you,

Yours faithfully,

For D.V. ELECTROMATIC PVT. LTD.

**Authorized Signatory** 





#### **ANNEXURE - I**

### **TECHNICAL SPECIFICATIONS**

1. Material of Sheet: CRCA sheet

**2. Sheet thickness:** AS PER TENDER thickness for All Panels.

**3. Material treatment:** Thorough chemical treatment with 7 tank process method for

degreasing, derusting and phosphating powder coating shall not be

less than 40 microns.

SIEMENS GREY (RAL-7032) shade powder coating paint will

be applied.

**4. Bus bar:** The bus bars will be insulated with PVC heat shrinkable

sleeves and supported SMC/DMC at Suitable intervals so as to withstand dynamic stresses developed in the event of short circuit of 50ka (RMS) and will withstand following

standard tests:-

(a) Continuity tests

(b) No load operation test

(c) H.T Test (2kV) for one minute.

(d) Insulation resistance test.

**6. Fault Level:** 35 KA

**7. Bus Bar Size:** As per BOQ

**8. Current Density:** 0.8A/Sq. mm. Current Density.

**9. Bus bar insulation** Heat Shrinkable Sleeves





## **ANNEXURE - II**

#### **PRICE SCHEDULE**

SR. NO.	DESCRIPTION OF ITEM	QTY	UNIT RATE (INR)	AMOUNT (INR)
1	SR NO 48	2	46,400.00	92,800.00
2	SR NO 49	1	62,900.00	62,900.00
3	SR NO 76	3	73,233.33	2,19,700.00
	TOTAL QUANTITY	6	TOTAL COST (INR)	3,75,400.00

In words: Rupees Three Lac Seventy Five Thousand Four Hundred Only

**NOTES:** 





## <u>ANNEXURE - III</u>

# **COMMERCIAL TERMS AND CONDITIONS**

**PRICE:** Ex works – IGC PATHANKOT (PB.)

**PACKING & FORWARDING:** Extra as per actual

**FREIGHT & INSURANCE:** Extra Freight & insurance.

**GST:** 18% or Actual As per Gst Taxation.

**OCTROI:** Extra as applicable.

**PAYMENT TERMS:** 50% in advance with confirmed order and balance against Performa

invoice before dispatch.

ORDER PLACEMENT: D.V. ELECTROMATIC PVT.LTD

**DELIVERY:** 6-8 Weeks from the date of approval of drawings.

**VALIDITY** Our offer is valid for 15 Days from the date of this offer and

thereafter subject to our confirmation.

**WARRANTY:** 18 Months from the date of supply or 12 months from the

commissioning whichever ends earlier.

**INSPECTION:** On intimation, prior inspection of the panels, if required, may be

carried out by the buyers authorized representative at our works at

IGC - Pathankot (pb.)

**ORDER AMENDMENTS**: Any change in specifications & other terms shall entail revision of

delivery and prices including statutory variations.

**FORCE MAJEURE:** We shall not be responsible for the failure or delay in order due to

acts beyond our control such as war, fire, labour problems, accidents, natural calamities, government acts or shortage of

material.

**COMMISSIONING CHARGES** 2500/Men days Testing, Commissioning and programming with

Loging, fooding and boarding in Customer scope. Unloading, Fixing, Laying cables and Installation of panels at site are not in our scope.

**Our Bank Details:** 

HDFC Bank
DALHOUSIE ROAD, PATHANKOT-145001
A/c # 50200012824476

IFSC Code: HDFC0002459