



REF NO: **DVEPL/20-21/6872/R0**

Date - 11-November-2024

TO,

GE (SOUTH) PATHANKOT - MES

Kind Attn.: XXX Mobile No.: XXX

Email ID:

Sub: QUOTATION FOR LT PANEL GES_PKT_51_2024-25 (2024_MES_680690_1)

Dear Sir,

We acknowledge with thanks the receipt of your valued enquiry regarding above mentioned subject. We are pleased to furnish our most competitive offer for your favorable consideration as under.

ANNEXURE - I: FABRICATION DETAILS & TECHNICAL SPECIFICATIONS

ANNEXURE- II: PRICE SCHEDULE

ANNEXURE- III: TERMS AND CONDITIONS

We hope the detailed BOQ & Tech Specs here under is as per your requirement.

Should you need any further clarification(s) please feel free to contact us. We look forward for an opportunity to serve you.

Thanking you,

Yours faithfully,

For D.V. ELECTROMATIC PVT. LTD.

Authorized Signatory





<u>ANNEXURE – I</u>

TECHNICAL SPECIFICATIONS

1. Material of Sheet: **CRCA** sheet

2. Sheet thickness: AS PER TENDER thickness for All Panels.

3. Material treatment: Thorough chemical treatment with 7 tank process

method for degreasing, derusting and

phosphating powder coating shall not be less than

40 microns.

SIEMENS GREY (RAL-7032) shade powder

coating paint will be applied.

4. Bus bar: The bus bars will be insulated with PVC heat

> shrinkable sleeves and supported SMC/DMC at Suitable intervals so as to withstand

dynamic stresses developed in the event of short circuit of 50ka (RMS) and will

withstand following standard tests:-

(a) Continuity tests

(b) No load operation test

(c) H.T Test (2kV) for one minute.

(d) Insulation resistance test.

6. Fault Level: 35 KA

7. Bus Bar Size: As per BOQ

8. Current Density: 0.8A/Sq. mm. Current Density.

9. Bus bar insulation Heat Shrinkable Sleeves





<u>ANNEXURE - II</u>

PRICE SCHEDULE

SR. NO.	DESCRIPTION OF ITEM	QTY	UNIT RATE (INR)	AMOUNT (INR)
1	SR NO 48	1	66,000.00	66,000.00
2	SR NO 49	2	64,300.00	1,28,600.00
3	SR NO 50	2	1,25,350.00	2,50,700.00
4	SR NO 51	2	18,650.00	37,300.00
5	SR NO 52	2	23,200.00	46,400.00
6	SR NO 52	2	26,250.00	52,500.00
	TOTAL QUANTITY	11	TOTAL COST (INR)	5,81,500.00

In words: Rupees Five Lac Eighty One Thousand Five Hundred Only

NOTES:





ANNEXURE - III

COMMERCIAL TERMS AND CONDITIONS

PRICE: Ex works – IGC PATHANKOT (PB.)

PACKING & FORWARDING: Extra as per actual

FREIGHT & INSURANCE: Extra Freight & insurance.

GST: 18% or Actual As per Gst Taxation.

OCTROI: Extra as applicable.

PAYMENT TERMS: 50% in advance with confirmed order and balance against Performa

invoice before dispatch.

ORDER PLACEMENT: D.V. ELECTROMATIC PVT.LTD

DELIVERY: 6-8 Weeks from the date of approval of drawings.

VALIDITY Our offer is valid for 15 Days from the date of this offer and

thereafter subject to our confirmation.

WARRANTY: 18 Months from the date of supply or 12 months from the

commissioning whichever ends earlier.

INSPECTION: On intimation, prior inspection of the panels, if required, may be

carried out by the buyers authorized representative at our works at

IGC - Pathankot (pb.)

ORDER AMENDMENTS: Any change in specifications & other terms shall entail revision of

delivery and prices including statutory variations.

FORCE MAJEURE: We shall not be responsible for the failure or delay in order due to

acts beyond our control such as war, fire, labour problems, accidents, natural calamities, government acts or shortage of

material.

COMMISSIONING CHARGES 2500/Men days Testing, Commissioning and programming with

Loging, fooding and boarding in Customer scope. Unloading, Fixing, Laying cables and Installation of panels at site are not in our scope.

Our Bank Details:

HDFC Bank DALHOUSIE ROAD, PATHANKOT-145001

A/c # 50200012824476 IFSC Code: HDFC0002459